Items of work	Unit	Sanctioned		Rate quoted in	
		Quantity	Rate	Figures	Words
			Rs. a. p.	Rs. a. p.	Rs.
9. Pointing with chunam mortar and thread lines	Sqr.	1·45	1 8 0		
10. White and colour washing, two coats.	,,	46·81	0 5 0		
11. Roofing with 1st class Mangalore tiles on teakwood batten 2″×1″ with wood oiling to reepers including nailing and fixing the eave tiles by a teak batten screwed down to the rafters and painted with chocolate.	,,	13·18	24 0 0		
12. Providing and fixing ridge tiles in mortar and pointed with cement	R.ft.	68	0 7 6		
13. Providing and fixing ventilating tiles in mortar and pointed with cement.	Each	16	1 8 0		
14. Honneywood work wrought and put-up with two coats of wood oiling	C.ft.	51·81	3 12 0		
15. Teakwood door frames 4″×3″ in section with 1½″ thick Honneywood battened shutters with iron clamps, fittings, wooden cleats, etc., complete	S.ft.	156	1 6 0		
16. Windows with 4″×3″ in section, teakwood frames and 1¼″ thick Honneywood battened shutters ¾″ diameter, iron bars, iron clamps and fittings, etc., complete	,,	60	1 12 0		
17. Providing and fixing stone pestle and mortar	Each set.	4	6 0 0		
18. Flooring with burnt stone jelly in lime mortar 3″ thick and over it 1½″ thick cement concrete and plastered with cement ½″ thick mixed with red ochre and cut into squares and finished complete	Sqr.	8·03	18 0 0		
19. Silicate painting, two coats	,,	5·28	3 0 0		
20. Wall shelves with 3″×4″ teakwood frame, 1″ thick Honneywood cross planks and Honneywood battened shutters 1¼″ thick with iron clamps and fittings, etc., complete	S.ft.	48	1 2 0		
21. Expanded metal frame work 2½″×2″ in section teakwood frames and doorways including painting two coats with silicate painting, etc., complete.	,,	246	0 12 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 24th January 1938.

Attention of the public is drawn to the Notification calling for tenders for Maintenance Work to Tumkur Amanikere, Register No. 1, Tumkur Taluk, in pages 86-87, Part VI in the *Mysore Gazette*, dated 20th January 1938.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th February 1938.

An earnest money of Rs. 300 in cash should accompany the tender.

Notification.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th February 1938, for diverting Marashettihalli Halla to Nittur Tank by constructing an *ane* across the Halla. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for diverting Marashettihalli Halla to Nittur Tank, Gubbi Taluk, by constructing an *ane* across the Halla" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer or his authorised representative after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Rates for the earthwork and new stone work tendered will be the average rates for the required leads and lifts at the respective heights of bund and no claims for enhancement of the same will be accepted.

14. No compensation will be allowable for the delay caused in starting the work or in payments, and any claim on these accounts will not be considered.

Abstract estimate for opening a new feeder channel from Marasettihalli Halla to Nittur Tank, Gubbi Taluk.

No.	Items of work	Per	Quantity	Rate
	I. Cutting the feeder channel bed with 10' side slopes 1 : 1.			Rs. a. p.
1	Cutting in average gravelly soil	C.yd.	63,949	0 5 0
2	Hard rock	,,	1,000	2 0 0
3	Constructing cart bridges	Each	2	200 0 0
4	Bed grade and other unforeseen charges	Lumpsum	..	160 0 0
5	Masonry head works at the head of feeder channel ..	,,	..	150 0 0
	II. Constructing a masonry Ane at A B 94 feet long at 108·00 with returns at 114·00.			
1	Excavating foundations approach channels and sundry items such as turfing, etc.	Lumpsum	..	100 0 0
2	Jelly concrete in surki mortar for the foundation of body wall and return	C.ft.	1,000	0 4 0

No.	Items of work	Per	Quantity	Rate Rs. a. p.
3	Burnt stone in surki mortar	C.ft.	6,808	0 6 0
4	Burnt stone slab 6″ dressed coping over Ane	S.ft.	250	0 8 0
5	Providing joggle	Each	9	1 0 0
6	Pointing with cement	Sqr.	33·36	6 0 0
7	Rough stone work	C.yd.	173	2 0 0
	III. Constructing an Ane at C D of Marasettihalli Halla and excavating approach channel from Ane C D to Ane A B length of approach channel will be three furlongs in length.			
1	Cutting gravelly soil for approach channel	C.yd.	6,673	0 5 0
2	Constructing a masonry Ane	Lumpsum	..	2,500 0 0
3	Widening the existing feeder channel from Pura tank to Nittur tank	,,	..	500 0 0

Notification dated 15th January 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th February 1938, for restoring Thyagatur Amanikere, Register No. 53 of Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 600 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Thyagatur Amanikere, Register No. 53 of Gubbi Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer or his authorised representative after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Rates for the earthwork and new stone work tendered will be the average rates for the required leads and lifts at the respective heights of bund and no claims for enhancement of the same will be accepted.

14. No compensation will be allowable for the delay caused in starting the work or in payments, and any claim on these accounts will not be considered.

Abstract estimate for restoring Thyagatur Amanikere (Breached tank), Nittur Hobli, Gubbi Taluk.

No.	Items of work	Per	Quantity	Rate		
	I. Bund R. L. 54·00.			Rs.	a.	p.
1	Jungle clearing and removing ant hills ..	Lumpsum	..	150	0	0
2	Cutting catches to slopes to receive fresh earth ..	,,	..	100	0	0
3	Earthwork with watering and tamping	C.yd.	8,140	0	4	6
4	Turfing	S.yd.	9,100	0	1	0
5	Raising old stone revetment with new jelly	C.yd.	417	1	0	0
6	New stone revetment with 3 miles lead	,,	1,655	2	4	0
7	Fixing new grade stones with figuring and painting ..	Each	46	2	8	0
8	Fixing B. M. stones	,,	2	3	0	0
9	Fixing registered No. and date stones	,,	1	5	0	0
10	Fixing guage stone	,,	2	15	0	0
	II. Sluice.					
1	Petty repairs to sluice	Lumpsum	..	150	0	0
	III. Waste Weir.					
	(*a*) New Masonry left end waste weir 49·00, 55 feet long.					
1	Earthwork excavation	Lumpsum	..	53	0	0
2	Burnt brick in surki mortar	C.ft.	100	0	5	0
3	Plastering with surki mortar	Sqr.	0·89	4	0	0
4	Burnt stone slabs 6″ thick dressed with joggle joints ..	S.ft.	66	0	12	0
5	New stone work, 3 miles lead	C.yd.	14	2	4	0
	(*b*) Raising left natural weir 47·50, 100 feet long.					
1	Earthwork excavation	Lumpsum	..	23	0	0
2	Jelly concrete in surki mortar	C.ft.	868	0	4	6
3	Burnt brick in surki mortar	,,	3,959	0	5	0
4	Plastering with surki mortar	Sqr.	23·00	4	0	0
5	Burnt stone slabs 6″ thick dressed with joggle joints ..	S.ft.	190	0	12	0
6	Rough stone work old with new jelly	C.yd.	259	1	2	0
7	Filling in field jelly	,,	173	0	12	0
	(*c*) Raising right natural weir 47·50, 40 feet long.					
1	Earthwork excavation	Lumpsum	..	12	0	0
2	Jelly concrete in surki mortar	C.ft.	448	0	4	6
3	Burnt brick in surki mortar	,,	2,129	0	5	0
4	Plastering with surki mortar	Sqr.	14·50	4	0	0
5	Burnt stone slabs 6″ thick dressed with joggle joints ..	S.ft.	100	0	12	0
6	Rough stone work old with new jelly	C.yd.	126	1	2	0
7	Filling in field metal	,,	73	0	8	0
	(*d*) Masonry right end waste weir 49·00, 65 feet long.					
1	Earthwork excavation	Lumpsum	..	16	0	0
2	Burnt brick in surki mortar	C.ft.	116	0	5	0
3	Plastering with surki mortar	Sqr.	1·03	4	0	0
4	Burnt stone slabs 6″ thick with joggle joints	S.ft.	78	0	12	0
5	Rough stone work new with new jelly	C.yd.	20	2	4	0
	IV. Unforeseen charges during execution ..	Lumpsum	..	271	0	0

P. RAJAGOPALAN,
Executive Engineer.